

Advanced Work Zone Safety Study Guide Index

Schedule - We will work until 4:30 the first day

Hopefully taking the exam by 2:30 the second day

Check List

Truck Mounted Attenuator Portable Changeable Message Sign (PCMS) Arrow Board

Letter "Failure to Perform"

Module 1- Introduction	1	22
Module 2 – Manuals and References	22	32
Module 3 – Fundamental Principals	32	39
Module 4 – Human Factors	39	57
Module 5 – Component Parts	57	71
Module 6 – Types of Temporary Traffic Control	72	80
Module 7 – Design Considerations	80	93
Module 8 – Traffic Control Devices	94	125
Module 8 – Traffic Control Plans	125	138
Module 9 – Night-Time Traffic Control	139	147
Module 10 – Other Considerations	147	166
Module 11 – EXAM		

Categories for TMP

*IIM-TE-351.5 TMP Requirements* 

IIM-241.7 – TE 351.5 Traffic Management Plan

Exercise 6 – Traffic Barrier & Channelizing Exercise

Exercise 6a – ROR Chart All Others

Exercise 6b – ROR Chart for Limited Access

Exercise 8 – Detour

*Exercise – drawing for detour* 

Exercise 9 – Bridge Replacement

Exercise – Tapers & Buffers

Exercise – Barrier

Urban Exercise Blank

ROR Charts

\_\_\_\_\_



# Work Zone Safety Device Check List – Truck Mounted Attenuator

Virginia Work Area Protection Manual (Section 6F-95) (Page 6F-77)

# When used:

- A. When closing a lane on four or more lane roadway with posted speed of 45 mph or greater
- B. On shoulders of multilane roadways with a posted speed of 45 mph or greater for operations with a duration greater than 60 minutes.
- C. On shoulders, ramps and loops or interstate and Limited Access highways
- D. When a mobile operation occupies all or part of the travel lane on a multi-lane roadway with a posted speed of 45 mph or greater
- E. For planned operations involving snooper trucks or bucket trucks regardless of the posted speed limit

F. Ot	ther locations where the Regional Traffic Engineer feels such protection is warranted
	Certification that the unit conforms to NCHRP 350 test level 3
	In good condition, i.e. no holes, major dents, etc.
45-degree	Rear Panel shall have alternate 6-inch-wide orange and black chevron sloped downward at a angle starting at the middle.
	Manufacturer's instructions available upon request (suggest they stay in the truck)
	The required weight of the support vehicle noted in the manufacturer's instructions
	A weigh ticket for the support truck (with specific identification to the truck.)
	The truck shall be parked in second gear or in park if automatic
	The parking brake shall be applied
	The wheels shall be aligned straight ahead
	THE WHEELS SHALL NOT BE CHOCKED (the manufacturer should tell you)
DATE IN	SPECTED:
SIGNATU	URE OF INSPECTOR:



# Work Zone Safety Device Check List – Portable Changeable Message Sign

Virginia Work Area Protection Manual (Section 6F-68) (Page 6F – 40-43)

### When Used:

- ✓ Ahead of the work area to advise of adverse conditions
- ✓ Ahead of the work area to advise of impending work/event
- ✓ Where speed is expected to drop substantially or suddenly
- ✓ Where queuing and delays are expected
- ✓ Where there are changes in the surface conditions
- ✓ Incident management
- ✓ Where there is a new road/travel pattern

### What to look for:

A.	Minimum of 7 feet above the road way in urban areas	
B.	Minimum of 5 feet above the road way in rural areas	
C.	Red and White conspicuity strip along the front	
D.	Tow vehicle completely removed from the unit and away from the taper	
Ε.	Outriggers/support legs deployed and leveled	
F.	When two or more are used, they must be 1000 feet apart and on the same s	ide
	f the road	
G.	Message in accordance with Appendix D of the Virginia Work Area Protect	tion
	Ianual	

### **Remember:**

When placed on the roadway or <u>within the clear zone</u>; there are always **4 Type II Channelizing Devices (Drums)** placed in front of the arrow board beginning at the front wheel and proceeding forward. No channelizing devices go at the rear wheel unless it is in addition to the other 4. See page 6F-43 in the Virginia Work Area Protection Manual.

When placed in the median where it is in both clear zones (each direction) drums are placed in advance of **BOTH** directions.



# Work Zone Safety Device Check List - Arrow Board

Virginia Work Area Protection Manual (Section 6F-69) (Page F-43-46)

### When Used:

- ✓ On the shoulder at the beginning of each taper
- ✓ On vehicles in a mobile operation
- ✓ in the 4 corner mode when blocking the shoulder
- ✓ If there is no room on the shoulder move up into the taper until it fits

✓

### What to look for:

A. \_\_\_\_\_Minimum of 7 feet above the road way
B. \_\_\_\_\_Red and White conspicuity strip along the front
C. \_\_\_\_\_Tow vehicle completely removed from the unit and away from the taper
D. \_\_\_\_\_Outriggers/support legs deployed and leveled
E. \_\_\_\_\_\_no lights out in the head for more than 30 minutes
F. \_\_\_\_\_\_one light out in the stem for the shift
G. \_\_\_\_\_\_center light always out
H. \_\_\_\_\_\_Support vehicle (if used) shall have a rotating amber high-intensity light

### Remember:

There are always **4 channelizing devices** placed in front of the arrow board beginning at the front wheel and proceeding forward. No channelizing devices go at the rear wheel unless it is in addition to the other 4. See page 6F-43 in the Virginia Work Area Protection Manual.

The channelizing devices are the same as are in the taper. i.e. cones if the taper is made up of cones and drums if the taper is made up of drums.



# COMMONWEALTH of VIRGINIA

DEPARTMENT OF TRANSPORTATION 1401 EAST BROAD STREET RICHMOND, VIRGINIA 23219 2000

Charles A. Kilpatrick, P.E. Commissioner

April 3, 2015

TO:

**Work Zone Traffic Control Training Instructors** 

FROM:

David B. Rush, WZS Training Committee Chairman

Re:

Failure to Perform Satisfactory Work Zone Traffic Control Techniques by Trained

Personnel

It has been brought to our attention that on occasion, Work Zone Traffic Control (WZTC) trained personnel have failed to apply the proper techniques to meet the requirements when installing, reviewing, or managing the installation and removal of work zone traffic control. The purpose of these training courses is to provide train personnel. In turn, trained individuals must apply this knowledge to provide safe work zones for workers, motorist, pedestrians, bicyclist and other road users. Failure to apply proper WZTC techniques affects not only safety but could have legal consequences if it contributes to a crash in a work zone.

Procedures are being develop to address suspension of a WZTC training verification card and the steps needed to release the suspension. Suspension of a training verification card will remove the responsibilities associated with the possession of a WZTC training card – meeting the requirements to install, review, make adjustments to and the removal of work zone traffic control or supervise those who perform these functions.

Until the procedures are finalized and released, current language in Section 105 of the VDOT Road and Bridge Specifications may be applied by VDOT Project personnel to those who fail to adequately apply the training they have received through the WZTC training courses.

105.05—Character of Workers, Work Methods, and Equipment

## (a) Workers

Workers shall have sufficient skill and experience to perform properly the work assigned to them. Workers engaged in special or skilled work shall have sufficient experience in such work and in the operation of equipment required to perform it properly and satisfactorily.

Any person employed by the Contractor or any subcontractor who, in the opinion of the Engineer, does not perform his work in a proper and skillful manner or is intemperate or disorderly shall, when directed in writing by the Engineer, be removed by the Contractor or subcontractor employing the person and shall not be employed again on any portion of the work without the written approval of the Engineer. If

the Contractor fails to remove the person or furnish suitable and sufficient personnel for proper prosecution of the work, the Engineer may withhold all monies that are or may become due the Contractor and may suspend the work until the Contractor has complied with the Engineer's directive.

Please provide a copy of this information to attendees of your training classes and impress upon them the seriousness of applying what you have taught them once they have adequately passed the examination and begun their duties as Basic, Intermediate, or Advance Work Zone Traffic Control trained personnel.

# Advanced Work Zone Traffic Control Training April 2015

1



2




















































































































































































# \*Work Area Protection Manual Revision 2 & Pocket Guide \*Work Area Protection Manual is Virginia's supplement to the MUTCD's Part 6 Temporary Traffic Control • WAPM establishes higher standards & provides clarification for work zone traffic control & typical traffic control layouts. • 2011 Revision 2 Sept. 2019 is the Latest edition of the WAPM. • Effective Sept. 1, 2019 for daily operations. • Effective for projects/contracts with ad dates on or after Jan 1, 2020. • Jan. 2020 is the latest Revision of the Pocket Guide

# \* 2011 VA WAPM Revision 1 Revised April 1, 2015

- •2011 Virginia WAPM Rev. 1 will still apply to projects advertised between Sept. 1, 2019 and December 31, 2019 until their completion.
- •2015 Pocket Guide is a supplement to the 2011 Rev 1 WAPM.

79

# \* WAPM Introduction



Provides Federal & State Regulations for TTC

- \* WAPM:
- \* It is not feasible to cover every conceivable situation
- · Illustrates many of the typical worksites
- **Describes many common conditions**
- Circumstances occur which are not specifically covered which require modifications

roduction (12)

80

# \* Term Definitions



- Similaris A statement of required, mand or specifically prohibitive practice regarding traffic control device(s).
  - Standards are labeled, and the text appears in bold large type.
  - The verb "shall" is typically used.
  - Standards are sometimes modified by Options. Module 2 - AWZTCT

# \* Term Definitions



- A statement of highly recommended practice in typical situations, with deviations allowed for engineering judgment (must be documented).
  - Guidance are labeled, and the text appears in large italicized type.
  - The verb "should" is typically used.
  - Guidance statements are sometimes modified by Options.

Module 2 - AWZTCT

82

## \* Term Definitions



- A statement of practice that is a permissive condition and carries no requirement or recommendation.
  - Options may contain allowable modifications to a Standard or Guidance.
  - Option statements are labeled and the text is underlined.
  - The verb "may" is typically used.
  - Guidance statements are sometimes modified by Options.

Module 2 - AWZTCT


83


# \* Term Definitions





- IT An informational statement that does not convey any degree of mandate, recommendation, authorization, prohibition, or enforceable condition.
  - Support statements are labeled, and the text appears in small font.
  - The verbs shall, should, and may are not used in Support statements.

Module 2 - AWZTCT

























































































































































Straight Path Consulting			
* Converting mph to fps			
*Multiply the speed in miles per hours by 1.47 to obtain the number of feet a vehicle travels is one second			
Example: 60 mph = (60)(1.47) = 88 fps 55 mph = 55 x 1.47 = 81 fps			
Module 4 - AWZTCT			

Straight Path  Consulting  Feet Traveled in One Second				
	Speed (mph)	Speed (fps)		
	25	37		
	35	51		
	45	66		
	55	81		
	60	88		
	65	96		
	75	110		
Module 4 - AWZTCT				

















































170

- \* In this module we will cover:
- How work zone types are determined
- •The six categories of work duration
- •The five component parts of a TTC Zone and discuss each.


Module 5 - AWZTC1























































































































































- •Involves stopping all traffic in both directions for a relatively short time to allow the work to proceed.
- After certain amount of time, driven by the traffic volume, the roadway is reopened.

Module 6 - AWZTCT

226





227





- Routing the traffic from one direction onto a portion of the median and roadway of the opposing traffic.
- May also incorporate lane constrictions.
- On higher speed roadways, Traffic barrier Service Concrete (TBSC) is used to separate the two directions of traffic.

Module 6 - AWZTCT










## \* Five Categories of Work Duration • Long-term Stationary: This is an activity that occupies a location more than 3 consecutive days. • Intermediate-term Stationary: This is an activity that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than 1 hour. • Short-term Stationary: This is a daytime activity that occupies a location for more than 1 hour, but less than 12 hours.





### \* Five Locations of Work Activity


- Outside the Shoulder Traffic control may be minimal and consist of a general warning only.
- On the Shoulder Motorists must be warned that work is near moving traffic, and the shoulder may not be available for emergency
- •On the Shoulder with minor encroachment -Traffic control encroaching upon the open travel lane must provide a minimum 11' lane width or 10' lane width on low volume roadways.



236

## \* Five Locations of Work Activity

• In the Median of a Divided Highway - Traffic control in both directions should be used and protection for workers may be necessary.



### \* Types of Roadways

- Limited Access Highway High speed, high traffic volume roadway, usually with multiple travel lanes and peak travel periods.
- Multilane Non-Limited Access Roadway May or may not be divided. Multiple travel directions to contend with, as well as geometrics (hills and curves).
- Two-Lane Roadway Traffic control must control the remaining lane, usually through flagging or temporary signals.

238

### \* Other Considerations

- Urban Street Low speed, high traffic volume during morning/evening peak travel periods, many entrances and business. Pedestrian traffic control may be required.
- Intersection May or may not be signalized. Multiple travel directions to contend with requiring coordinated traffic control.
- Total Roadway Closure Safest, quickest for performing work activities, requires approval, planning, and detour traffic control.



Consulting

239














# \* Essential Data Checklist (cont.) \*Other • Jurisdictions involved • Business access & parking areas • School bus routes • Fire district & location of fire stations • Hospitals • Policies on worker or motorist safety • Incident management plans

## \* Essential Data Checklist (cont.)

- \*Other (cont.)
  - Possibility of inclement weather
  - •Start and end of construction season
  - Holiday and recreational activities
  - Environmental impacts
  - Public/Property owners concerns
  - Wetlands
  - Archeological studies
  - Special Events



247





248














\* Prop-off Definition


\*A drop-in elevation, parallel to the adjacent travel lanes, with slopes steeper than 4:1.


\*"NON RECOVERABLE"


\*If drop-off occurs within the clear zone due to construction and maintenance, warning signs, wedges, and/or protection devices are required!

\*\*Investigation\*\*

\*





































\* Use of Intelligent Transportation
Systems (ITS) in Work Zones

\*An applicable strategy to:
•Manage the work zone traffic in real-time

•Informs motorists of work zone activities to avoid delays by utilizing alternate routes

•Provides guidance and creates safer operation for the motorists and workers

\*\*Traight Path Consulting\*\*

### \* Use of Intelligent Transportation Systems (ITS) in Work Zones

- \*Triggers to use ITS:
- Long duration projects
- Presence of or proposed ITS deployment
- High expectations of long delays/queues
- Existing and potential high incident (crash) locations



271




272


### \* Regulatory Traffic Control Strategies


- Strategies that rely on regulatory signing with law enforcement.
- The messages conveyed on regulatory signs can be enforced
- Refer to IIM-LD-93 and agreement with the Virginia State Police.

































### The PCMS message should brief and convey:

- 1. The problem or situation that the road user will encounter ahead,
- 2. The location of or distance to the problem or situation, and
- 3. The recommended driver action.





286



287


				*	PCM:	S Mess	ages	
***********	, Portable Changeable Messages fo			Table D-2, Portable C	hangeable Menag	es for Advance Cloures o	e Road Week	
TTC Number	PHASE 1	PHASE 2	PHASE 3 or Additional PCMS may be used	77 ST / CLOSED / 311-8/31 RT 55 / CLOSED / 301-8/1 EXIT 123 / CLOSED / 341-16				
Example	Line 1 / Line 2 / Line 3	Line 1 / Line 2 / Line 3	Line 1 / Line 2 / Line 3	RD WORK / CLOSED / MON-FRI				
TTC-1	RIGHT / SHOULDER / WORK							
TTC-2	FLAGGER / AHEAD	PREPARE / TO / STOP						
TTC-3	SLOW / MOVING / WORK	RIGHT / SHOULDER / CLOSED		Table D-3, Unaccepta	U- B			
	RIGHT / SHOULDER / CLOSED	1,000,000		1 more 10-3, Unaccepts				
TTC-5	RIGHT/SHOULDER/CLOSED	RIGHT / LANE / NARROWS				SEAWARE BEWARE		
TTC-6	RIGHT / SHOULDER / CLOSED 'RIGHT / SHOULDER / CLOSED	TRUCKS / USE / RT LANE		BE ALERT (any form or combination of BE ALERT messages)  CARE (any form or combination of CARE messages)  INFO CARE  INFO CARE				
TTC-7	LANE(S) / SHIFT / RIGHT	RIGHT / SHOULDER / CLOSED		CAUTION (any form or combination of CAUTION messages)  LIFE CAUTION				
	"LANEIS)/SHIFT/RIGHT	TRUCKS / USE / RT LANE		NOTICE (myssages)				
TTC-8	BOTH / SHOULDER / CLOSED	RIGHT / PULL OFF / AHEAD		WARNING, WARN (any form or combination of WARN messages)				
11.000	"BOTH/SHOULDER/CLOSED	TRUCKS / USE / RT LANE						
TTC-9	SLOW / MOVING / WORK	PREPARE / TO / STOP				****		
TTC-10	LFT LANE / CLOSED / AHEAD	SLOW / MOVING / WORK		Table D. C. Abbrests	Hour That Shall h	a Drad Oaks on Burtable C	hangeable Messages Signs	
TTC-12	RT LANE / CLOSED / AHEAD 2 RT LANE / CLOSED / AHEAD	SLOW / MOVING / WORK SLOW / MOVING / WORK			Standard	Prompt Word That	Prompt Word That Shor	
TTC-13	RT LANE / CLOSED / AHEAD SLOW / MOVING / WORK	SLOW / MOVING / WORK DO / NOT / PASS		Work Message	Abbreviation	Should Precede the Abbreviation	Follow the Abbreviatio	
	"SLOW / MOVING / WORK	PREPARE / TO / STOP	DO / NOT / PASS	Access	ACCS AHD		Road	
TTC-15	LEFT/LANE/CLOSED	MERGE / INTO / RT LANE		Ahead	AHD	Fog		
	"HEAVY / TRAFFIC / AHEAD	EXPECT/DELAYS		Blocked Bridge	BUKD BUKD	(Name)		
	"HEAVY / TRAFFIC / AHEAD	PREPARE / TO / STOP		Cannot	CANT	(Name)		
TTC-16		MERGE / INTO / LFT LANE		Center	CNTR		LANE	
	"RT LANE / CLOSED / MM123	MERGE / INTO / LFT LANE		Chemical	CHEM		SPILL	
	"HEAVY / TRAFFIC / AHEAD	EXPECT / DELAYS		Condition	COND	Traffe		
	"HEAVY / TRAFFIC / AHEAD	PREPARE / TO / STOP		Congestion	CONS	Traffic		
TTC-17	LEFT / LANE / CLOSED	MERGE / INTO / RT LANE		Construction	CONST		Ahead	
	*LFT LANE / CLOSED / MM123	MERGE / INTO / RT LANE		Crossing Do Net	XING		= =	
	"HEAVY / TRAFFIC / AHEAD	EXPECT/DELAYS		Do Not Downtown	DWNTN		Traffic	
TTC-18	"HEAVY / TRAFFIC / AHEAD	PREPARE / TO / STOP MERGE / INTO / RT LANE		Eastbound	F-8ND		11800	
110-18	2 LEFT / LANES / CLOSED *2 LFT LN / CLOSED / MM 123			Emergency	EMER			
	"HEAVY / TRAFFIC / AHEAD	MERGE / INTO / RT LANE EXPECT / DELAYS		Entrance, Enter	ENT	0-0		
	"HEAVY / TRAFFIC / AHEAD	PREPARE / TO / STOP		Exit	EX	Next	3,-3	
TTC-19		MERGE/INTO/RT LANE		Express	EXP		ane	
110019	"LET LANE / CLOSED / MM 123	MERGE / INTO / RT LANE					0	
	"HEAVY / TRAFFIC / AHEAD	EXPECT/DELAYS						
_								














Traffic Control Device - Signs

Classification of Signs:

Regulatory

Warning


Construction


Incident Management


Guide

Recreational and Cultural Interest Areas






































		* Requi	red Sheeting for	Signs			
0		it Orange Pri n angle) Lens					
Minimum Coefficient of Retroreflection $R_A$ ( $R_A$ =Candelas per foot-candle per square foot)							
	Observation Angle (°)	Entrance Angle (°)	Fluorescent Orange				
	0.2	-4	140				
	0.2	+30	90				
	0.2	+40	24				
	0.5	-4	90				
	0.5	+30	50				
	0.5	+40	15				
	1.0	-4	10				
	1.0	+30	5				
	1.0	+40					
		For rigid signs	Module 8	- AWZTCT			

















### Arrow Boards are used: • in lane closure operations \* Arrow Board • on shadow (protection) vehicles • on vehicles in mobile operations











































































				CCC	ncho	anic
			ce Concrete Deflection Table ased on VDOT projects are show	n in bold	and highligh	red.
	FHWA Code	Manufacturer	Device Description	Test Level	Dynamic Deflection	Anchorage (a)
* Appendix A;	B-79	Pennsylvania DOT	12.5' Long F-Shape temporary barrier w/plate connection.	TL-3	8-7"	80"
* Pages A-13 & 14	B-63	Barrier Systems, Inc.	Quickchange Moveable Barrier (QMB)	TL-3	4-6"	10'- 4"
*Anchorage - length of barrier	B-54	Virginia DOT	20' Long F-Shape barrier w/pin & loop connection.	TL-3	6'	60"
needed upstream, downstream of the WZ to ensure maximum		Rockingham Precast	12' Long F-Shape w/T-Bar connection.	TL-3	3'- 10"	60"
deflection is not exceeded	B-40	Barrier Systems, Inc.	Narrow Quickchange Moveable Barrier.	TL-3	2-11"	(b)
*No materials or equipment	able 3,	Acceptable Longitu	dinal Steel Barriers			
should be stored in deflection	FHWA Code	Manufacturer	Device Description	Test Level	Dynamic Deflection	
zone	B134	Energy Absorption Systems, Inc.	Vulcan Barrier	TL-3	13'- 2"	302 Lg (a)
	B134	Energy Absorption Systems, Inc.	Vulcan Barrier with Anchoring System VAS	TL-3	6'- 11"	(b)
	B-131	Highway Care, Inc.	Barrier Guard 800	TL-3	4- 11"	(c)
	B-158	Highway Care, Inc.	Barrier Guard 800 MDS	TL-3	0 3.	(d)
	B-176A	Hill & Smith, Inc.	Zone Guard Standard	TL-3	6'- 4"	(e)
	B-176A	Hill & Smith, Inc.	Zone Guard Minimum Deflection	TL-3	1'- 4"	(f)




























362

### \* Pavement Marking & Eradication

- Pavement Markings and markers are the primary source of delineation for motorist at night.
- Lack of markings, or improper eradication of existing markings, are one of the areas most sited in work zone litigation.
- The following questions should be asked for every construction project . . .































\* What is a Traffic Control Plan?

- Based on a Transportation Management Plan (TMP)
- A plan that details the traffic control for a specific project
- Consistent with the complexity of the project
- Adjusted to field condition


The TCP is the culmination of everything we have learned in this course!



376



377





- Effective on all work zone activities within state right of way and on all streets and highways that have been accepted into the State Highway Systems.
- Temporary Traffic Control, Public Information, and Traffic Operations strategies for managing work zone impacts to traffic.
- Roles and responsibilities for project teams in developing TMPs during the preliminary engineering and construction phases of a project
- Categorizes projects based on the complexity of the construction.

   Module 9 AWZTI



Module 9 - AWZTCT

Straight Path

380

adjacent roadways.

\* Transportation Management Plan Requirements
Type A Projects

VDOT's


Maintenance, Permit and Utility

Processes

• VDOT Contract Administrator/Manager, Private
Contractor/Developer, or Utility develops and submits
plan to the appropriate VDOT work group

• Submitted plan is reviewed by the VDOT work group
with assistance, as needed, by the Regional Traffic
Engineering and Operations staff



















# \*Transportation Management Plan Requirements IIM-LD-241/TED-351 Work Zone Safety and Mobility Type B Projects Complex projects consisting of lane closures, traffic shifts and /or detours Requires a traffic impact assessment Requires a Temporary Traffic Control Plan with Detail Plans, Typical Sections and/or special details Requires a Public Communications Plan for high volume roadways and a Transportation Operations Plan for work zones greater than ½ mile in length

391

## \* Type B and C TCP Should Address... 1. The location of all advance warning signs and lighting units 2. Temporary pavement markings 3. Location of temporary barriers and attenuators 4. Temporary drainage design 5. Channelizing devices at special locations 6. Location of special devices \*\*Type B and C TCP Should Address... 1. The location of all advance warning signs and lighting units 2. Temporary pavement markings 3. Location of temporary barriers and attenuators 4. Temporary drainage design 5. Channelizing devices at special locations 6. Location of special devices

392




## \* Type B and C TCP Should...

- Resolve any conflicts between permanent signing and markings and work zone signing and markings
- Key strategies such as service patrol, police, public service announcements, Highway Advisory Radio (HAR), night work, ITS, etc.



394



395


## \* Type B and C Other TCP Considerations


- Must allow room for equipment to properly perform its function
- May use flaggers, diversions, etc. to allow for a safe operation
- •May impose an "operational limit" for a piece of equipment
- Must avoid conflicts with other equipment/utilities





































































































\* Factors Affecting Glare

• Distance between driver and the luminaire
• Height of the luminaire
• Direction the luminaire is aimed


Adjusting these factors controls glare!






















































































During a Project Work Zone Review it was noted:


In the TTC Plan that a pedestrian path was to be provided during construction but no specific details were provided

No alternate path was provided for pedestrians


A. DRIFE FIRED.

A. DRIFE FIRE









## Changes in the 2011 WAPM

6D - Pedestrian and Worker Safety

Pedestrians with disabilities requirements:


- If a pedestrian facility was accessible to pedestrians with disabilities, the footpath provided during TTC should also be accessible.
- Use of audible devices for TTC information
- Use of barriers that are detectable by a person using a cane due to visual constraints.
- Pathways at least 60" wide, or 60" x 60" passing space every 200 feet.


482







































## PROJECT CATEGORIES

In recognition that projects undertaken by VDOT vary in size, complexity, and risk, a project ranking system has been defined to group projects by category based primarily on level of complexity and risk. The categorization of projects allows for a statewide consistent assignment of the appropriate scheduling provision to ensure that the appropriate level of scheduling efforts needed to establish and maintain schedule control on the project is applied.




Figure 1-2: Project Category – Level of Complexity and Schedule Risk

The VDOT project ranking system consists of six categories representing varying levels of complexity and risk ranging from very low to very high. Category M is the lowest, which represents typical maintenance projects and schedule type work. Categories I through V represent typical single-contract construction projects ranging from simple to very complex. Characteristics of each project category are described as follows:

- 1. Category M Category M represents typical maintenance contracts and seasonal schedule type work of very low complexity and risk, where specific timeframes for accomplishing the work is generally not a major constraint rather a full construction season is generally given to allow for a flexible schedule. Such projects, therefore, do not require the level of scheduling efforts needed for typical construction projects.
  - A. Criteria for Category M Projects Category M projects must generally meet the following criteria:
    - i) Typical maintenance and schedule type work; or

ii)	Seasonal contracts with contract duration of one construction season or less
	(Time is not a major constraint); or

- iii) Simple repairs or straight-forward maintenance work; and
- iv) Minimal traffic impact or limitations to the Work; and
- v) No involvement with other major construction or improvement projects.

B.	<b>Examples</b> of	of Category	M Projects -	The following	are typical	Category M	projects
----	--------------------	-------------	--------------	---------------	-------------	------------	----------

<b>Examples of Category M Projects</b> – The following are typical Category M projects
— Pavement schedules (Asphalt overlay, surface treatments & slurry seals);
— Bridge joint repairs;
— Bridge painting (minimum traffic impact);
— Guardrail improvements;
— Curb and gutter repair/replacement;
— Raised pavement marker installation, lens replacement;
— Pavement marking schedules;
— Minor Bridge repair (District wide, minor miscellaneous);
— Rumble strip installation;
— Slope slide repair, scour repair;
— Ground mounted sign maintenance/replacement;
— Incidental concrete repair;
— Pipe culvert rehabilitation;
— Bridge cleaning;
— Retaining wall/ Sound wall repair;
— Signal maintenance & repair (District wide).

**C.** Category M Scheduling Requirements – Category M scheduling requirements are based on the basic scheduling information necessary for the Department to coordinate all work required to complete the Contract and to communicate with the public. The schedule information will also be used to plan for and manage the Department's cash flow, resources, and traffic. The Category M Progress Schedule submittal consists of:

- i) A Schedule of Operations in the form of a Narrative to provide a written description of the overall plan and sequence of operations; as well as a general schedule of operations to indicate when each segment of the work will be completed. The schedule may be provided in a tabular or bar-chart format.
- ii) A weekly rolling two-week look-ahead schedule will also be required to show the detailed schedule of work planned for the following two weeks. The lookahead schedule may be provided in a tabular or bar-chart format.
- 2. Category I Category I is the lowest level of the project ranking system for typical construction projects, which represents simple and low risk projects. Such projects include typical small, simple, and short duration construction projects with very limited and straight-forward operations. Category I may also include other simple and low risk single season or less construction projects with minimal or no limitations to the Work, whose plan of operations and schedule can be effectively communicated in written words.
  - A. Criteria for Category I Projects Category I projects must generally meet the following criteria:
    - i) Contract duration of one construction season or less (typically short durations); or
    - ii) Estimated contract value of \$1 million or less; and
    - iii) Limited items of work; and
    - iv) Simple operations with favorable conditions; and
    - v) Minimal traffic impact or limitations to the Work; and
    - vi) Does not include utility adjustments or relocations; and
    - vii) Contract does not contain any Special Provisions for special time-related conditions, such as Interim Contract Milestones, A+B Bidding, Insensitive/Disincentive, or Lane Rental; and
    - viii) Project has no major materials delivery restrictions, environmental impacts, delayed right-of-way acquisitions or access, or other similar constraints and restrictions.

On a case by case basis, certain single-season simple and low risk projects with estimated contract value greater than \$1M that generally meet the criteria listed above may qualify as Category I, as determined by the Area Construction Engineer (ACE);

On a case by case basis, certain Federal Oversight (FO) maintenance projects or time sensitive maintenance projects with traffic impact may qualify as Category I, as determined by the ACE. Such projects may include concrete pavement repairs or overlay work on major corridors or certain relatively complex time sensitive maintenance projects that are involved with major construction or improvement projects. In such cases, the ACE should consult with the State Construction Scheduler for concurrence.

- **B.** Examples of Category I Projects The following are typical Category I projects:
  - Rural grade, drain, & pave of unpaved roads (may include minor horizontal & vertical alignment changes and rural rustic projects with drainage work);
  - Minor bridge deck repair & concrete overlay (may include multiple bridges);
  - Break, seat, & overlay concrete pavement;
  - Spot improvements (multiple locations any of: incidental concrete, minor widening, enhanced pavement marking, & sign installation);
  - Building demolition in advance of construction projects;
  - Retaining wall installation or extensive repair;
  - Minor bridge substructure repairs (with traffic impact);
  - Bridge painting (multiple locations or with traffic impact);
  - Minor urban reconstruction & improvement (could include curb & gutter and sidewalks; new or extended turn lanes);
  - Surface reclamation, sub-grade stabilization & overlays;
  - Bridge steel repair (with traffic impact);
  - Signal installation Site specific (w/o intersection improvements, no regional on-call installations);
  - Overhead sign installation & lighting installations (multiple locations & or significant amount of lighting);
  - Simple concrete pavement repair and/or asphalt overlay (major corridor, minimum traffic impact).
- **C.** Category I Scheduling Requirements Category I scheduling requirements are based on the basic scheduling information needed to communicate the Contractor's work plan and to assess progress of the Work. The schedule information will also be used to plan for and manage the Department's resources, expenditures, traffic, as well

as to communicate with the general public. The Category I Progress Schedule submittal consists of:

- i) A Narrative to provide a written description of the overall plan and sequence of operations;
- ii) A Tabular Schedule to show the detailed schedule of work and key dates associated with the work;
- iii) A Progress Earnings Schedule (Form C-13C) to assess progress of the Work.

A Baseline Progress Schedule is required at least 7 calendar days prior to beginning the Work. Progress of the work will be monitored relative to the anticipated earnings or the project milestone dates. The Progress Schedule needs updated only when either the plan or the work has changed significantly; at such time, the Engineer will request submission of a revised schedule to include the updated information and the revised plan to complete the remaining work.

- 3. Category II Category II is the second level of the project ranking system for typical construction projects, which represents slightly complex and low to medium risk projects. Category II projects are typical low volume single season construction projects with a limited number of straightforward contiguous, linear, or repetitive operations; and low to medium traffic impact or constraints. Such projects include, but are not limited to single or two lane widening or turn lane projects in an urban setting. Category II may also include certain multi-season slightly complex and low risk projects. Such projects may include, but are not limited to long duration projects with minimal constraints or traffic impact, such as projects involving simple repetitive operations performed at multiple locations; or widening projects in a rural setting, involving a limited number of straightforward contiguous or linear operations, whose schedule can be effectively communicated in a time-scaled bar-chart.
  - A. Criteria for Category II Projects Category II projects must generally meet the following criteria:
    - i) Contract duration of one construction season or less (may be two construction seasons, but involve simple linear or repetitive operations); or
    - ii) Estimated contract value generally less than \$3 million; and
    - iii) Limited number of straightforward contiguous or linear operations; and
    - iv) Low to medium traffic impact; and
    - v) Typical conditions and limitations to the work; and
    - vi) May include minimal utility adjustments; and

- vii) Contract does not contain Special Provisions for special time-related conditions, such as Contract interim milestones, Incentives/Disincentives, A+B bidding, or Lane Rental, etc.; and
- viii) Project has no major materials delivery restrictions, environmental impacts, right-of-way acquisitions, or other similar constraints and restrictions.

On a case by case basis, certain slightly complex and low to medium risk projects with estimated contract value over \$3M that generally meet the criteria listed above may qualify as Category II, as determined by the ACE.

On a case by case basis, certain high-volume Federal Oversight (FO) maintenance projects or relatively complex maintenance projects that involve multiple items of work, multiple schedule constraints, or significant traffic impact may qualify as Category II, as determined by the ACE. Such projects may include concrete pavement repairs or overlay work on major corridors or certain relatively complex time sensitive maintenance projects that are involved with major construction or improvement projects. In such cases, the ACE should consult with the State Construction Scheduler for concurrence.

## B. Examples of Category II Projects – The following are typical Category II projects:

- Urban grade, drain, & pave projects of low to medium complexity;
- Rural new construction or reconstruction grade separation roadway and bridge projects (low to medium size and complexity);
- Complex reconstruction and improvements, including widening and multiple turn lanes that may include utility adjustments;
- Major bridge substructure repairs (with low to medium traffic impact);
- Bridge deck replacements, such as multi-span or over railroads;
- Major bridge deck repair & concrete overlay (multi-span or over railroads);
- Intersection improvements with lighting and/or signal installation;
- Bridge & drainage structure replacements (frequently single span with limited approach work);
- Major drainage improvements;
- Complex concrete pavement repair and/or asphalt overlay (major corridor, significant traffic impact);
- Multi-season bridge painting (with low to medium traffic impact).

- **C.** Scheduling Requirements for Category II As the amount of work, project duration, or level of complexity and associated risks increases, a scheduling tool that can graphically depict the sequence and timing of the activities in a time-scale format is required to effectively communicate the Contractor's plan of operations and the intended sequence of progress. The Category II scheduling requirements are based on the bar-chart method. The Category II Progress Schedule submittal consists of:
  - i) A Narrative to provide a written description of the overall plan and sequence of operations;
  - ii) A Bar-chart Schedule to graphically depict the general sequence and timing of work and key dates associated with the work;
  - iii) A Progress Earnings Schedule (Form C-13C) to assess progress of the work.

The Category II Baseline Progress Schedule is required at least 7 calendar days prior to beginning the Work. The Bar-chart Progress Schedule and Progress Earnings Schedule will be updated monthly to reflect the actual status of work accomplished and the proposed plan to complete the remaining work. The schedule will be revised accordingly when either the plan or the work has changed significantly; at such time, the Engineer will request submission of a Revised Progress Schedule to include the updated information. Progress of the work will be monitored relative to the planned earnings and project milestone dates.

- 4. Category III Category III is the middle level of the project ranking system for typical construction projects, which represents moderately complex and medium risk projects. Category III projects are typical medium size multi-season construction projects with limited number of concurrent operations and constraints. Such projects include, but are not limited to new construction, reconstruction, extension, or widening/improvements of medium size roadway/bridge projects with typical constraints and/or traffic impact. Category III projects may also include certain medium to large size multi-season projects of relative complexity and low risk. Such projects may include, but are not limited to long duration projects with typical constraints and minimal traffic impact, such as limited span bridge or interchange projects in a rural setting.
  - A. Criteria for Category III Projects Category III projects must generally meet the following criteria:
    - i) Med-size projects with contract duration generally spanning 2-3 construction seasons; or
    - ii) Estimated contract value generally between \$3M and \$10M; and
    - iii) Limited number of concurrent work-paths; and
    - iv) Medium limitations to the work and traffic impact; and

- v) Limited number of utility adjustments; and
- vi) Contract does not contain Special Provisions for special time-related conditions, such as Contract interim milestones, Incentives/Disincentives, A+B bidding, or Lane Rental, etc.; and
- vii) Project has no major materials delivery restrictions, environmental impacts, right-of-way acquisitions, or other similar constraints and restrictions.

On a case by case basis, certain moderately complex and medium risk projects with estimated contract value over \$10M that generally meet the criteria listed above may qualify as Category III, as determined by the ACE.

On a case by case basis, certain high-volume Federal Oversight (FO) maintenance projects or relatively complex maintenance projects that involve multiple items of work, multiple schedule constraints, and/or significant traffic impact may qualify as Category III, as determined by the ACE. Such projects may include major concrete pavement repairs or overlay work on major corridors or certain relatively complex time sensitive maintenance projects that are involved with major construction or improvement projects. In such cases, the ACE should consult with the State Construction Scheduler for concurrence.

- **B. Examples of Category III Projects** The following are typical Category III projects:
  - Intersection improvements, including widening and multiple turn lanes with utilities, lighting and/or signal installation (with medium complexity and traffic impact);
  - New roadway/bridge construction or extension projects (medium size, complexity, and traffic impact);
  - Bridge deck replacements (multi-span, medium traffic impact);
  - Bridge & drainage structure replacements (limited span with approach work);
  - Bridge reconstruction/widening projects (medium size, complexity, and traffic impact).
- C. Scheduling Requirements for Category III As the number of operations or level of complexity and risk grows a scheduling tool that will allow for adequate planning and scheduling of concurrent activities with considerations for associated constraints is required to plan and execute the Work. Such scheduling method will require that activity relationships are added to establish inter-dependencies between related activities to form network paths to aid the project staff to efficiently plan for and manage the level of resources required to complete the work as planned. The longest continuous network path through the project then defines the project critical path and

the overall time to complete the project. The Category III scheduling requirements are based on the Critical Path Method (CPM). The Category III Progress Schedule submittal consists of:

- i) A Narrative to provide a written description of the overall plan and sequence of operations;
- ii) A CPM Schedule to graphically depict when the activities that make up the project can be performed;
- iii) A Progress Earnings Schedule (Form C-13C) to assess progress of the work.

The Category III Baseline Progress Schedule submission is required within 30 calendar days after the Contract Notice to Proceed (NTP) date. The CPM Progress Schedule and Progress Earnings Schedule will be updated monthly to reflect the actual status of work accomplished and the proposed plan to complete the remaining work. The schedule will be revised accordingly when either the plan or the work has changed significantly; at such time, the Engineer will request submission of a Revised Progress Schedule to include the updated information. Progress of the work will be monitored relative to the planned earnings and project milestone dates.

- 5. Category IV Category IV is the fourth level of the project ranking system for typical construction projects, which represents complex and high risk projects. Category IV projects are typical medium to large size multi-season construction projects with multiple concurrent operations and constraints. Such projects include, but are not limited to new, reconstruction, extension, or widening/improvements of medium to large roadway/bridge projects with substantial constraints and/or traffic impact. Category IV projects may also include certain med-size high-risk projects of relative complexity that include provisions for special time-related constraints or conditions. Such projects may include, but are not limited to major intersection widening/improvement projects in an urban setting with significant traffic impact, involving any combination of the following: utility/drainage adjustments, multi-lane roadway construction, lighting and/or traffic signals.
  - A. Criteria for Category IV Projects Category IV projects must generally meet the following criteria:
    - i) Medium to large size projects with contract duration generally spanning 3 or more construction seasons; or
    - ii) Estimated contract value generally between \$10M and \$75M; or
    - iii) Contract contain Special Provisions for special time-related conditions, such as Contract interim milestones, Incentives/Disincentives, A+B bidding, or Lane Rental, etc.; and
    - iv) Multiple concurrent work-paths; and

- v) Complex construction staging, phasing, or MOT issues; and
- vi) Complex constructability issues; and
- vii) Substantial traffic impact and limitations to the work; or
- viii) May include major utility relocation/adjustments; and
- ix) Project has no major materials delivery restrictions, environmental impacts, right-of-way acquisitions, or other similar constraints and restrictions.

On a case by case basis, certain relatively complex and high risk projects with estimated contract value less than \$10M that generally meet the criteria listed above may qualify as Category IV, as determined by the ACE. In such cases, the ACE should consult with the State Construction Scheduler for concurrence.

On a case by case basis, certain relatively complex and high risk projects with estimated contract value over \$75M that generally meet the criteria listed above may qualify as Category IV, as determined by the ACE.

- **B. Examples of Category IV Projects** The following are typical Category IV projects:
  - Major urban intersection improvements, including widening and multiple turn lanes with utilities, lighting and/or signal installation (medium to large size, complex, and significant traffic impact);
  - Rural/Urban new construction or reconstruction grade separation roadway and bridge projects (medium to large size, complex, major corridor);
  - Major bridge deck replacements (substructure repairs, multi-span, multi-lane, major corridor, with significant traffic impact);
  - Major bridge & drainage structure replacements (multi-span with extensive approach work);
  - Major widening projects (medium to large size and complexity, major corridor, with significant traffic impact).
- **c.** Scheduling Requirements for Category IV As the size, complexity, and associated risks grow, a scheduling tool that will allow for adequate planning and scheduling of manpower, equipment, and expenditures is required to accomplish the Work. Category IV schedules will also allow for an accurate assessment of the current status of the individual activities and the overall progress of the Work. The Category IV scheduling requirements are based on the Category III requirements with additional requirements for cost-loading. The Category IV Progress Schedule submittal consists of:

- i) A Narrative to provide a written description of the overall plan and sequence of operations;
- ii) A Cost-loaded CPM Schedule to graphically depict when the activities that make up the project can be performed;
- iii) A Progress Earnings Schedule (Form C-13CPM) to assess progress of the work:
- iv) A 30-day look-ahead schedule to depict work planned for the next period.

The Category IV Baseline Progress Schedule submission is required within 45 calendar days after the Contract Notice to Proceed (NTP) date. The CPM Progress Schedule and Progress Earnings Schedule will be updated monthly to reflect the actual status of work accomplished and the proposed plan to complete the remaining work. The schedule will be revised accordingly when either the plan or the work has changed significantly; at such time, the Engineer will request submission of a Revised Progress Schedule to include the updated information. Progress of the work will be monitored relative to the planned earnings and project milestone dates.

- 6. Category V Category V is the highest level of the project ranking system for typical construction projects, which represents complex and very high risk mega-projects. Category V projects are typical very costly and multi-season construction projects with a considerable number of concurrent operations and significant constraints. Such projects include, but are not limited to new, reconstruction, extension, expansion, or widening/improvements of very large and/or very complex roadway/bridge projects with substantial constraints and/or traffic impact. Category V projects are also typical very long duration multi-phased mega-projects with multiple roadway segments and/or several bridge structures on major corridors that may involve multiple contracts or construction projects. Such projects typically involve major roadway/bridge construction/widening, very complex multiple-span bridges, or major interchange work on major corridors.
  - A. Criteria for Category V Projects Category V projects must generally meet the following criteria:
    - i) Very large projects with contract duration generally spanning 3 or more construction seasons; or
    - ii) Estimated contract value generally greater than \$75M; and
    - iii) Contract contain Special Provisions for special time-related conditions, such as Contract interim milestones, Incentives/Disincentives, A+B bidding, or Lane Rental, etc.; and
    - iv) Considerable number of concurrent work-paths; and

- v) Complex construction staging, phasing, or MOT issues; and
- vi) Complex constructability issues; and
- vii) Substantial traffic impact and limitations to the work; and
- viii) Substantial number of right-of-way acquisitions and/or relocations; or
- ix) Major material delivery restrictions; or
- x) Significant utility relocation/adjustments; or
- xi) Major environmental or community impact.

On a case by case basis, certain relatively complex and very high risk projects with estimated contract value less than \$75M that generally meet the above listed criteria may qualify as Category V, as determined by the ACE. In such cases, the ACE should consult with the State Construction Scheduler for concurrence.

- **B.** Examples of Category V Projects The following are typical Category V projects:
  - Major rural/urban new construction or reconstruction grade separation roadway and bridge projects (large size, complex, major corridor, significant traffic impact);
  - Major widening projects (large size, complex, major corridor, significant traffic impact);
  - Major interchange projects (large size, complex, major corridor, significant traffic impact);
  - Major bridge deck replacement projects (large size or multiple bridges, complex, major corridor, significant traffic impact);
  - Individual Category III or IV level projects that are included in multiple-contract mega-projects like Woodrow Wilson, Springfield Interchange, etc.).
- c. Scheduling Requirements for Category V As the size, complexity, and associated risks grow, a scheduling tool that will allow for adequate planning and scheduling of manpower, equipment, and expenditures is required to accomplish the Work. Category V schedules will also allow for an accurate assessment of the current status of the individual activities, progress of selected major operations that will have the greatest influence on the schedule, and the overall progress of the Work. The Category V scheduling requirements are based on the Category IV requirements with additional requirements for a qualified and dedicated project scheduler/coordinator, resource-loading, and commodity-tracking (progress of selected controlling items of work).

For individual Category III or IV level projects that are included in multiple-contract mega-projects such as Woodrow Wilson, Springfield Interchange, etc., contractors will be required to develop and maintain their schedules in a collaborative structured environment within the master-project schedule database. The Category V Progress Schedule submittal consists of:

- i) A Narrative to provide a written description of the overall plan and sequence of operations;
- ii) A Resource-loaded and Cost-loaded CPM Schedule to graphically depict when the activities that make up the project can be performed;
- iii) A Progress Earnings Schedule (Form C-13CPM) to assess progress of the work;
- iv) A Commodity Progress Report (Form C-13COM) to assess progress of the selected commodities (controlling items of work);
- v) A detailed 4-week look-ahead schedule with a 1-week look-back.

The Category V Baseline Progress Schedule submission is required within 60 calendar days after the Contract Notice to Proceed (NTP) date. The CPM Progress Schedule, Commodity Progress Report, and Progress Earnings Schedule will be updated monthly to reflect the actual status of work accomplished and the proposed plan to complete the remaining work. The schedule will be revised accordingly when either the plan or the work has changed significantly; at such time, the Engineer will request submission of a Revised Progress Schedule to include the updated information. Progress of the work will be monitored relative to the planned earnings, anticipated progress of the selected commodities, and project milestone dates.





# Advanced Work Zone Traffic Control Training **Traffic Barrier/Channelizing Exercise**

TASK: By using Appendix A of the Virginia Work Area Protection Manual, determine what type of device is needed to protect the work area and the motorists. If the determination is for use of concrete barriers, also list the barrier flare/slope ratio needed in the transition.

1.	A 12'x 10' double box culvert extension is being located 6 feet from the edge of the travelway on a two-lane rural secondary route. The posted speed limit is 45 mph, and the vehicle count is 15, 000 vehicles per day (VPD). What device or barrier should be used if the hazard is to exist for 4 months?
	Accident exposure (f) from frequency factor curve:
	Accident factor (P) = $f x t x L$ :
	Type of device:  Barrier flare/slope ratio (if required):
	Barrier flare/slope ratio (if required):
2.	A project is adding an outside climbing lane on one side of an Interstate highway for a
	length of 1.3 miles. The posted speed limit is 55 mph and the vehicle count is 36,000
	VPD. What device should be used if the work zone is expected to last 26 weeks?
	Accident exposure (f) from frequency factor curve:
	Accident factor (P) = f x t x L:
	Type of device:
	Barrier slope ratio (if required):
3.	An excavation for a stormwater management basin is within 8 feet of a 2 lane urban highway. The length and width of the basin is 1200' x 400' respectively with a maximum depth of 5'. The posted speed limit is 35 mph and the vehicle count is 10,000 VPD. The clear zone area between the curb and the proposed basin has a 6:1 slope. Construction is expected to last 6 weeks. What device is needed?
	Accident exposure (f) from frequency factor curve:
	Accident factor (P) = f x t x L:
	Type of device:
	Barrier slope ratio (if required):



## WORK ZONE TRAFFIC CONTROL TRAINING


#### Work Zone Exercise Number 8

#### Intersection Design

Design a work zone traffic control for the following condition:

A sink hole has been discovered on the eastbound lanes of I-24 and the interstate must be closed completely and a detour installed. Route 900 to Route 10 will be the detour route. Speed limit for the intersection roadways as follows:

✓ Route 46 ✓ Route 900 ✓ Route 10	55 mph
	is 12". Due to lack of space on the work sheet, just show traffic control for southbound Route 10 ontrol will be the same.
Your mission (should	you choose to accept it) is to develop traffic control for the intersecting roadways.
Traffic must be contr	olled continuously by flaggers for a 7 day period.
What TTC figures wo	uld you reference?
What is the sign space	ing for each intersection?
Route 46	
Route 900	
Route 10	
Channelizing device s	spacing and what type?
Merging Taper Lengt	h?
Buffer Space Length?	





#### WORK ZONE TRAFFIC CONTROL TRAINING

#### Work Zone Exercise Number 9

## **Bridge Replacement**

Design a work zone traffic control for the following condition:

A bridge must be replaced on the westbound lanes of I24. Traffic will be diverted onto the eastbound lanes causing a two-way situation. The length of the work zone is 1,000'. Existing traffic volumes are 30,000 ADT. Truck volumes are very high, therefore; shoulder widening has been installed to allow for the installation of traffic barrier service. The speed limit will be reduced to 55 mph and 12' wide lanes must be maintained. The median width is 16'' plus 4' shoulders. The total lane shift is 16 + 4 + 4 + 12 = 36'. The operation is expected to be completed in 20 days.

What TTC's would you reference?					_	
Signs? 1	2	3	4	5	6	
Sign Spacing? _					_	
Channelizing D	evice?	Sı	pacing?			
Merging Taper	Length?		Shifting Taper Ler	ngth		
Buffer Space Le	ength ?					
Do you think th	he barrier should	be secured to the ro	adway?			
Why or why no	ot?					
What is the cle	ear zone for this r	oadway?				
Do you need in	mpact attenuator	rs?				
Why or why no	o t?					



# Advance Work Zone Traffic Control Training **Tapers and Buffer Spaces Exercise**



TASK: By using the 2011 VA WAPM, determine the minimum taper and buffer lengths needed for the following work zone activities.

1.	A right lane closure as shown in TTC 16.0 on a 45 mph posted primary route with a travel lane width of 12 feet and a shoulder width of 10 feet.				
	Length of Shoulder Taper:  Length of Merging Taper:  Length of Buffer Space:				
2.	As shown in TTC 40.0, the 11 foot wide travel lanes on a multilane secondary route are being shifted over toward the right shoulder 10 feet to accomplish a three day work activity. What is the length of the shoulder and shifting tapers and buffer space for the 35 mph posted roadway (the shoulders are 8 feet wide)?				
	Length of Shoulder Taper:  Length of Shifting Taper:  Length of Buffer Space:				
3.	An inside lane closure is needed for one day as shown in TTC-17.0. What is the shoulder, merging, and buffer space lengths for the 55 mph limited access highway with 12 foot wide travel lanes and 10 foot wide shoulders?				
	Length of Shoulder Taper:  Length of Merging Taper:  Length of Buffer Space:				



TASK: Design a TTC Plan for a project that requires pavement repairs on Eastbound Interstate 66 at the on ramp from Route 234 North.

The actual work is approximately 400 feet of the right lane. This will take up 14 feet of the right lane and about 10 feet of the acceleration lane. This will prohibit the full length of the acceleration lane to be used.

The repair will consist of removing and replacing 2" of surface and 8" of base.

The work will take approximately ????? hours to complete.

\_\_\_\_\_\_

- Route 234 is a major route with approximately 50,000 VPD
  - The speed limit is 45 mph
- The Route 234 ramp to eastbound Interstate 66 is two 12' lanes
  - The speed on the ramp is 35 MPH
- Interstate 66 is 4 through lanes 14" wide
  - o The shoulder width is 10 feet
  - The speed limit in this area is 60 MPH
- This area is normally congested with constant backups during normal rush hours. Frequently, this area remains congested after 9:00 a.m. The Engineer reserves the option to extend rush hour restrictions in these cases.
- The nearby asphalt plants are limited to production between 5:00 a.m. and 11:30 p.m.
  - The plants all continuous mix drum plants
  - o The storage capacity of the 3 silos are 300 tons each
  - o The silos will hold asphalt at 350 degrees for 6 hours
  - Asphalt weighs approximately 115 pounds per square yard inch

\_\_\_\_\_\_

Indicate all facets of this Traffic Control Plan to include but not be limited to:

- 1. What signs are required on each of the 3 roadways?
- 2. What is their spacing?
- 3. Show how you plan to physically move traffic away from the work area.
- 4. Indicate all traffic control devices you plan on using and their approximate lengths and locations
- 5. Will you require exceptions to the standards shown in the Virginia Work Area Protection Manual?
- 6. What other factors influence the plan?

#### VIRGINIA DEPARTMENT OF TRANSPORTATION

# **LOCATION AND DESIGN DIVISION**

## INSTRUCTIONAL AND INFORMATIONAL MEMORANDUM

GENERAL SUBJECT: Work Zone Safety and Mobility	NUMBER: IIM-LD-241.7 IIM-TE-351.5				
SPECIFIC SUBJECT:	DATE: January 3, 2017				
Transportation Management Plan Requirements	SUPERSEDES: IIM-LD-241.6 IIM-TE-351.4				
LOCATION AND DESIGN DIVISION APPROVAL:	TRAFFIC ENGINEERING DIVISION APPROVAL:				
B. A. Thrasher, P.E.	R. J. Khoury, P.E.				
State Location and Design Engineer	State Traffic Engineer				
Approved December 12, 2016	Approved December 8, 2016				

Changes are shaded.

$\alpha$	ID		NIT		1		٨I
CL	ハ	К	IV		v	0	N

• This memorandum was revised to replace Regional Traffic Engineer with "responsible District Traffic Engineer", effective January 25, 2017.

## **EFFECTIVE DATE**

These instructions are effective upon receipt.

#### **POLICY**

- The Virginia Department of Transportation is committed in providing safe and efficient movement of motorized and non-motorized traffic through or around roadway work zones as well as providing protection for workers and equipment located within work zones. VDOT will focus on roadway visibility and functionality of temporary traffic control in work zones and traffic flow through the work zone. Emphasis will begin with the preliminary engineering stages and carried through to the completion of all work, including post construction reviews.
- Compliance with this guidance is consistent with the Department's goal of reducing work zone crashes and improving travel time thereby benefiting all citizens of the Commonwealth. This guidance outlines recommended procedures to be followed and identifies responsibilities to achieve safer work zones with minimal impact on the traveling public.

VDOT, through this directive, is extending this requirement to all work zone
activities within state right of way and on all streets and highways that
have been accepted into the State Highway System regardless of the
funding source as well as all other projects receiving State and/or Federal
funding.

## **BACKGROUND**

- In September 2004, the Federal Highway Administration (FHWA) published the Final Rule on Work Zone Safety and Mobility, 23 CFR 630 Subpart J. This rule, referred to as Work Zone Safety and Mobility, applies to State and local governments that receive Federal-aid highway funding. Transportation agencies are required to comply with the provisions of the Rule by October 12, 2007. This rule updates and broadens the former regulation, "Traffic Safety in Highway and Street Work Zones," to address present and future work zone issues.
- The policy provisions in the Final Rule on Work Zone Safety and Mobility:
  - Requires agencies to implement a policy for the systematic consideration and management of work zone impacts on all Federal-aid highway projects. Furthermore, it encourages agencies to implement the policy for non-Federal-aid projects and programs.
  - Requires the policy to address work zone impacts throughout the various stages of the project's development and construction. The agency must consider work zone impacts during project development, management of work zone impacts during construction, and assessment of work zone performance after implementation. The agency must also consider communication with the public before and during the project.
  - Recognizes the state policy may vary based on the characteristics and expected work zone impacts of individual projects or classes of projects.
  - Requires the development of transportation management plans.

For additional information on the Final Rule on Work Zone Safety and Mobility, follow these links:

http://www.ops.fhwa.dot.gov/wz/resources/final\_rule.htm (Regulation, Guidance and Examples);

http://www.ops.fhwa.dot.gov/wz/practices/factsheets/factsheets.htm (Best Practices).

NCHRP Synthesis 208, Development and Implementation of Traffic Control Plans for Highway Work Zones.

TYPICAL WORK ZONE MANAGEMENT STRATEGIES

Various work zone management strategies may be employed to minimize traffic delays, thereby improving mobility as well as traveler and worker safety and completing the construction work in a timely manner while maintaining access for businesses and residents. The following set of strategies is not meant to be all-inclusive, but to present a number of suggestions for consideration while developing transportation management plans. A more extensive listing and general information on work zone management strategies may be accessed at the following web sites:

http://www.ops.fhwa.dot.gov/wz/rule\_guide/sec6.htm#tab62 and http://www.ops.fhwa.dot.gov/wz/resources/publications/trans\_mgmt\_plans/trans\_mgmt\_plans.pdf

The strategies are divided into three broad groups which are captioned as: 1)
Temporary Traffic Control, 2) Public Information; and 3) Transportation
Operations. Each of these groups is further defined by the specific items listed below.

## • Temporary Traffic Control Strategies:

- Control strategies
- Traffic control devices
- Project coordination, contracting and innovative construction strategies

## Public Communication Strategies:

- Public awareness strategies
- Motorist information strategies

### Transportation Operations Strategies:

- Demand management strategies
- Corridor/network management strategies
- Work zone management strategies
- Traffic/incident management strategies

#### **GENERAL GUIDELINES**

This section provides guidelines to be used by Project Managers, Roadway Designers, Traffic Engineers, Work Zone Safety Coordinators and Communication Managers for acquiring the information to develop a Transportation Management Plan (TMP). Project personnel shall involve the FHWA Area Engineer in each of the project's milestones on federal oversight projects. These guidelines require the evaluation of work zone traffic control and communication strategies beginning at the Scoping Activities and continued throughout the Project Development Process (PDP) and during all phases of construction. For additional information on the PDP, follow this link:

http://www.virginiadot.org/business/resources/Project Management Online Guide.pdf. Also see LD-436 Quality Control Check List, available at: http://vdotforms.vdot.virginia.gov/SearchResults.aspx?strFormNumber=LD-436

Specific work requirements are noted in the Project Development Process for each milestone, as are the Project Management forms that are to be submitted at the milestones. All Temporary Traffic Control Plans shall be in compliance with the information published in the Virginia Work Area Protection Manual. Any deviations from the Virginia Work Area Protection Manual must be approved by the responsible District Traffic Engineer (DTE) and noted in the plans.

- Initial Scoping Meeting The Project team shall use field observations, available crash data, and other relevant operational information to discuss preliminary work zone management strategies in conjunction with alternative project options and design schemes. Relevant operational information should include but is not limited to, project definition (scope, project's complexity level, roadway and traffic characteristics, and TMP type), construction phasing/staging of equipment and materials, pedestrian and bicycle routes, as well as temporary traffic control, public communications and transportation operations strategies. The Project Manager shall request that the responsible District Traffic Engineer (DTE) begin acquiring traffic and crash data and explore possible alternate/detour routes. A preliminary cost estimate for the project's traffic management plan shall be developed by the Project Manager at this milestone. The Project Manager shall request that a preliminary Public Communications Plan be drafted by the District Communications Manager.
- Final Scope / Preliminary Field Inspection The Project Team shall utilize traffic and crash data and the preliminary Sequence of Construction (SOC) plans to identify safety and mobility issues during the proposed construction and begin developing the project's preliminary TMP. The responsible District Traffic Engineer (DTE), working with the Project Team, shall propose the project's TMP that consists of temporary traffic control, public information, and transportation operations strategies, as appropriate. The Roadway Designer shall incorporate the recommended TMP into the projects initial roadway plans.
- Public Hearing Team Meeting Review of the preliminary TMP as incorporated by the Roadway Designer (includes the Temporary Traffic Control Plan as well as the Public Communications Plan and Transportation Operations Plan if required) must be completed by the responsible District Traffic Engineer (DTE) and Regional Operations Director as applicable. Recommendations/corrections submitted by the responsible District Traffic Engineer (DTE)/Regional Operations Director (ROD) that are accepted by the Roadway Designer in collaboration with the project team are to be incorporated into the preliminary TMP by the Roadway Designer prior to the Public Outreach/Public Hearing and Design Approval.
- Field Inspection Meeting The Roadway Designer shall complete the project's TMP for review by the project team during the Constructability and Work Zone Review stage for the Detailed Design Phase of the Project Development Process. Accepted recommendations/corrections submitted by the project team are to be incorporated into the TMP by the Roadway Designer prior to proceeding to the next phase of the project's development.

The Project Team shall review the TMP to ensure that all comments and concerns have been addressed. The responsible District Traffic Engineer shall review the TMP to check that all safety information and crash data have been incorporated into the TMP.

- Pre-Advertisement Conference The Roadway Designer shall complete the project's final TMP for review during the Constructability, Work Zone and TMP Review stage in the Final Design and ROW Acquisition Phase of the Project Development Process. Accepted recommendations/corrections submitted by the project team shall be incorporated into the final TMP by the Roadway Designer prior to proceeding to the next phase of the project's development. The Project Team shall review the TMP to ensure that all comments and concerns have been addressed. The TMP cost shall be finalized for the constructability review held prior to the Pre-Advertisement Conference milestone.
- Implementing the Transportation Management Plan During the first day of the new work zone traffic pattern, the project's Manager and project's Work Zone Safety Coordinator shall inspect the work zone to ensure compliance with the TMP. On the third to fifth day of implementation of the TMP's new work zone traffic pattern, the Regional Work Zone Safety Coordinator and the project's assigned Work Zone Safety Coordinator shall conduct an on-site review of the work zone's performance and inform the contractor all required changes to the TMP for implementation to enhance the work zone's safety and mobility. All such changes shall be documented. If the project is a federal oversight project, the FHWA Area Engineer shall be afforded the opportunity to review all such changes prior to implementation. An on-site review of the project's work zone traffic control by the Regional Work Zone Safety Coordinator, Project's Manager/Work Zone Safety Coordinator, District Safety Engineer, and the Contractor shall be conducted within 48 hours of any fatal incident/crash within This review shall be recorded on the Work Zone Safety the work zone. Checklist, Form TE-97000.
- Evaluation of the Transportation Management Plan A performance assessment of the project's TMP including area—wide impacts on adjacent roadways should be performed by the project's designated Work Zone Safety Coordinator during construction as circumstances dictate. Any recommendations and comments shall be communicated to the construction inspection team in writing for appropriate changes to the TMP. A review of the overall effectiveness of the project's TMP shall be completed during the Post Construction Meeting and included with the Post Construction Report. A copy of the specific information on the effectiveness of the project's TMP will be forwarded to the State Traffic Engineer for review.

The following guidance is provided to ensure the Project Team understands their role and responsibilities in the development of the project's TMP. Team members from the design disciplines/work group noted below shall have direct responsibilities for the proper development of the TMP during each stage of the Project Development Process.

The Project Manager shall solicit comments from other design disciplines such as Structure and Bridge, Environmental, Materials, etc, as appropriate, to confirm that all safety and mobility concerns are addressed. All team members shall be provided an opportunity to review the TMP prior to each milestone team meeting.

For projects that do not follow the Project Development Process, the Designer, Project Manager or the Contract Administrator will ensure the TMP and the component plans (Temporary Traffic Control, Public Communication and Transportation Operations Plans) are included in the project and contract documents. The development process should be established at scoping with the plans developed based on consultation with, and guidance from, the applicable discipline.

## Project Team:

The Project Manager, with the project team, will review the project at each milestone to ensure appropriate action is taken to reduce work zone impacts on the public. Responsibilities of the project team include a TMP Design Checklist Review Form that is available at: TMP Design Checklist.

## • Responsible District Traffic Engineer (DTE):

In order to promote the safety of workers as well as the safe and efficient movement of traffic through the project's work zone, the responsible DTE shall consider various temporary traffic management strategies and provide the project team with the following recommendations. The responsible DTE shall review the TMP to assess that all that the applicable information is included in the project's TMP:

- Temporary traffic management strategies
- Lane width(s) and the number of travel lane(s) and turn lane(s) to be maintained
- o Traffic impact assessments/analysis on the temporary traffic control plan
- Identify all signal phases within the work zone and on all detour/alternate routes
- Allowable work activity hours
- On-site and off-site detour routes
- Information on the use and placement of all temporary traffic control devices including barrier and channelization devices
- Type and placement of all signs, message boards, arrow boards, and TMA's
- Type and location of temporary pavement markings and markers
- Access to all businesses and private dwellings
- Post construction assessment of the Work Zone Traffic Impact
- Quantities for all temporary traffic control devices

## Regional Operations:

In order to promote the safety of workers as well as the safe and efficient movement of traffic through the project's work zone, the Regional Operations Director shall consider various transportation management strategies and provide the Roadway Designer and the project team with the following recommendations. The Regional Operations Director shall review the TMP to check that the applicable information is included in the project's TMP:

- Temporary transportation operations strategies
- Incident/emergency management plan
- o Use of ITS for traffic monitoring and queue detection
- Surveillance of work zone traffic using CCTV, loop detectors, etc.
- Use of safety service patrols
- Contact information for Transportation Operations Centers (TOC) and incident management
- o Traffic impact assessments/analysis on the temporary traffic control plan
- Identify all signal phases within the work zone and on all detour/alternate routes
- Allowable work activity hours

## • Location and Design (or Contract Administrator as appropriate):

Shall ensure the proper design and presentation of all aspects of the TMP by providing the following detailed information in the plan assembly:

- Profile, alignment, superelevation and lane widths for all traffic lanes, turning lanes, lane shifts and diversions not identified on existing roadways
- Earthwork/grading that must be completed prior to the next construction phase
- Utility work that can be completed within the project's guidelines for the TMP
- Ensure that all utilities will not conflict with temporary traffic control and other safety devices for all phases of construction.
- o Identification of all temporary pedestrian and bicycle routes.
- Identification of all temporary pavement locations and temporary drainage items
- Illustrations of the placement of all temporary signs, message boards, arrow boards, TMA's, barriers, attenuators, temporary pavement markings and markers, existing pavement marking eradication, and placement of Group I and II devices in the temporary traffic control plans for all construction phases (excluding temporary lane and shoulder closings)
- o Identification of all emergency pull-off areas
- Identification of all construction vehicle and equipment ingress and egress locations (for Temporary Traffic Barrier applications)
- Identification and notation of all signal phases within the work zone and all detour routes
- Complete TMP typical sections
- Complete special design details, special cross section and insertable sheets if applicable

Provide quantities for all temporary traffic control devices

## Structure and Bridge:

Shall ensure the proper design and presentation of specific aspects of the TMP pertaining to structures by providing the following:

- Movement, staging and use of cranes, other large equipment and materials
- Need for and placement of temporary bridge parapet and traffic barrier service
- Need for the setting of beams over traffic
- Use of temporary bridges
- Need for demolition over traffic
- Placement of the above information in the plan assembly in narrative or illustrated format

#### Communications

Shall ensure that the transportation management plan is communicated to appropriate key audiences (motorists, law enforcement, emergency services, businesses, residents, elected officials and media). Strategies will include:

- Development of project-specific communications plan to keep key customers informed about construction-related impacts before and during the construction;
- Communication and promotion of ways commuters can avoid construction-related delays, i.e. rideshare, telework, public transportation;
- Development of a crisis communications plan which outlines steps to be taken during a major incident and includes emergency contact information; and,
- Determination of the need for and types of community meetings needed to inform the public on the various aspects of the construction project

## Right of Way:

Shall ensure the proper design and presentation of specific aspects of the TMP by providing the following:

 All temporary/permanent easements needed for construction are included in the plans

# Project Constructability Work Group:

Shall ensure that the project can be constructed according to the Plan Assembly, the Sequence of Construction and the TMP by reviewing the project documents and ensuring that:


- Right of way is provided for the placement of construction equipment and materials
- Access is provided to the work area(s) for construction equipment and materials
- Consideration has been given for, methods of deep utilities and large diameter pipe construction.
- Adequate time is provided to complete the construction
- Utility plans have been coordinated with all phases of construction
- o Adequate drainage is maintained during construction
- Appropriate traffic control and an information campaign is provided for the setting of bridge beams or other operations requiring total roadway closures and detours
- All identified safety and mobility issues have been addressed for any unusual construction methods
- The project can be built as designed with the minimum necessary road closures and detours to avoid major recurring traffic impacts

#### PLAN REQUIREMENTS

This section provides guidance to Project Managers for establishing a project's TMP requirements based on the project's level of complexity. These guidelines categorize a project into one of three types of transportation management. The project's type identifies the **minimum** TMP requirements and recommendations to be used by Project Managers, Roadway Designers, responsible District Traffic Engineer, Regional Operation Directors and Communications Managers for developing TMP. In general, the TMP shall consist of a traffic control plan and, as required, public information and a transportation operations plan. The specific project level requirements for plan content are listed by project type. Any deviation from the requirements noted below will require the review and approval of the State Traffic Engineer.

### Work Area Access Considerations:

The Temporary Traffic Control Plan (TTCP) should address the need for access to the work area. This is a constructability issue in which the designer addresses the question of how the contractor will move materials and equipment into the work area safety with a minimum of disruption to traffic. This is a particularly critical issue on high speed roadways such as Limited Access highways, especially if temporary traffic barrier is used to protect work areas. Consideration should be given to the design and construction of temporary acceleration and deceleration lanes for the construction equipment. The following should be considered in the planning, design and operation of work zones:



- Anticipate types of work zones that typically create ingress/egress problems. Examples are work spaces requiring work vehicles to merge in/out of high-speed traffic and work activities that will generate frequent delivery of materials such as paving projects, bridge projects, and the delivery/movement of fill materials.
- Access into/out of the work space meeting the requirements in the Virginia Work Area Protection Manual shall be included in the Temporary Traffic Control Plan.
- Adequate acceleration/deceleration space for work vehicles should be provided.
- The location of access openings should meet the sight distance requirements listed in Appendix A of the Virginia Work Area Protection Manual. In extreme conditions, lane closures may need to be considered.
- Construction access openings in temporary traffic barrier should be planned per Appendix A of the Virginia Work Area Protection Manual to ensure that the blunt ends of barrier walls are properly protected. The barrier or channelization devices should be planned in a manner as to not create a sight distance problem for equipment operator or motorists.
- Ingress/egress condition may justify a lowering of the speed limit during this activity. Any reduction in the posted speed limit must be authorized by the responsible District Traffic Engineer and based on an engineering study per Traffic Engineering Division Memorandum IIM-TE-350.
- Warning signs ("Construction Entrance X" and "Trucks Entering Highway") are available for ingress/egress conditions at work area accesses and should be used when appropriate. Special warning signs may be necessary. All warning sign(s) noting work zone access activities shall be covered/removed when the daily work activity ceases.

# Type "A" Projects (Project Management Project Category I & II)

- Typical Projects: No-Plan, Minimum Plan, Single Phase Construction, Maintenance Projects, Utility and Permitted Work
- Project Type: Simple project widening of pavement or adding turn lanes or entrances. Sequence consists of temporary lane closures and flagging operations with no shifting of traffic onto temporary pavement and with two-way traffic operation maintained at all times or at new construction locations with no existing traffic. Temporary Traffic Control plans that only reference the Work Area Protection Manual do not requiring sealing and signing (refer to Traffic Engineering Division Memorandum IIM-TE-362).
  - Impact on Traffic: Lane closures and time restrictions should comply with the Regional Operation's lane closure policies. If the proposed work cannot be completed within the Regional Operation's allowable lane closure time periods, an assessment of the Work Zone Traffic Impact will be completed using a traffic analysis tool recommended in VDOT's Traffic Operations and Safety Analysis Manual (TOSAM).
    - http://www.virginiadot.org/business/resources/TOSAM.pdf. Lane closures, the use of traffic control devices and their placement, Public Information and Traffic Operations Plans will be approved by the Regional Operations Director with implementation based on the traffic impact evaluation and the Regional Operations Director's approval.

## Major Components:

## Temporary Traffic Control Plan

Major components will consist of General Notes, Typical Sections, and if needed Special Details. Each component should provide the following information (this information may be presented in a narrative format with illustrations/sketches as necessary):

#### General Notes which:

- Identify the project's TMP Type
- Identify the work zone location.
- Identify the length and width of the work zone.
- Identify the lanes affected by the project work.
- Note the hours the work zone will be active.
- Identify potential location(s), within the R/W, for construction equipment and material storage.
- Define the proposed traffic control by referencing the specific Typical Traffic Control Standard(s) listed in Virginia's Work Area Protection Manual and/or by referencing a Special Detail(s).
- Note any entrances, intersections or pedestrian access points that will be affected by the work zone or by the traffic control devices.
- Identify the major types of travelers (such as truckers, commuters, residents, etc.)

## Typical Sections which:

o Illustrate lane configuration(s) in the work zone.

# Special Details which:

- Show schematically the placement of all traffic control devices and locations of safe access into/out of the work space by work vehicles.
- Place all traffic control devices in accordance with the standards contained in Virginia's Work Area Protection Manual and the Manual on Uniform Traffic Control Devices.
   Detail for any traffic control device not illustrated in the Virginia Work Area Protection Manual will be included in the plan.
- Follow symbol conventions for identifying traffic control devices per Virginia's Work Area Protection Manual and the Manual on Uniform Traffic Control Devices.
- Show all details, dimensions and explanatory notes required to execute the traffic control plan.

#### Public Communications Plan

A Public Communications Plan is recommended for roadways when traffic volumes exceed the minimum number of vehicles/hour/lane or delay times established by the responsible District Traffic Engineer for lane closure periods. The Public Communications Plan shall provide the following information (this information may be presented in a narrative format):

- A process to notify the Project Manager/Residency Engineer/Administrator of scheduled work plans and traffic delays.
- A process to notify the Project Manager/Residency Engineer/Administrator, Regional Operations Manager and the Public Affairs staff of any unscheduled traffic delays.

### Transportation Operations Plan

A Transportation Operations Plan is recommended for roadways when the work space is greater than ½ mile in length and/or with reduced-width travel lanes. The Transportation Operations Plan shall provide the following information (this information may be presented in a narrative format as part of the Temporary Traffic Control Plan):

- A process to notify the Regional Transportation Operations Center (TOC) to place lane closure information on the 511 system and VA-Traffic.
- A contact list of local emergency response agencies.
- Procedures to respond to traffic incidents that may occur in the work zone.
- A process to notify the Project Maintenance of Traffic Coordinator / Project Manager/Resident Engineer / Administrator, District Work Zone Safety Coordinator / responsible District Traffic Engineer, the Regional Operations Manager and Public Affairs Manager of any incidents and expected traffic delays.
- Procedures to clear the incident and restore normal project traffic operations.
- Details of the process to review incidents for the purpose of modifying the Temporary Traffic Control Plan to reduce the frequency and severity of such incidents.

## Type "B" Projects (Project Management Project Categories III & IV)

 Typical Projects: Moderate level of construction activity with the primary traffic impact limited to the roadway containing the work zone.

DEVEROUT PRODUCTION TO

- Project Type: Moderately complex project pavement widening or bridges for additional thru lanes and pavement rehabilitation. Sequence consists of lane closures to one or both directions with shifting traffic that may include temporary pavement or detours for the duration of the work. If detour routes are used they typically will remain in place 24 hours per day for the duration of the work. Project will be constructed over several phases and may include bridge replacements or new bridges, new interchanges, modifying existing interchanges or a new construction location with existing traffic crossing the construction area.
  - Impact on Traffic: An assessment of the Work Zone Traffic Impact will be completed using a traffic analysis tool recommended in VDOT's Traffic Operations and safety Analysis Manual (TOSAM) <a href="http://www.virginiadot.org/business/resources/TOSAM.pdf">http://www.virginiadot.org/business/resources/TOSAM.pdf</a>. Lane closures and detour routes will be implemented based on this evaluation. All lane closures and time restrictions shall comply with the Regional Operation's lane closure policies, with any deviations requiring the approval of the Regional Operations Director.

#### Major Components:

Temporary Traffic Control Plan

Major components shall consist of Detail Plans, Typical Sections, and as required Special Details/Cross Sections/Profiles. Each component shall provide the following information per construction phase. This information shall be placed on a plan sheet.

- Detail Plans which include all the information listed for Type A Projects plus:
- o Detail drawing(s) containing the following information:
  - Identify the project's TMP Type
  - Narrative describing the sequence of construction
  - Type and location of all temporary signs for the work zone and all detour routes
  - Type and location of all temporary pavement markings
  - Type and location of all temporary pavement
  - Type and location of all temporary barriers
  - Type and location of all impact attenuator/end treatments/Fixed-Object-Attachments (FOA)
  - Locations of safe access into/out of the work space by work vehicles.
  - Locations of emergency pull-off areas.
- Document/detail how all entrances, intersections or pedestrian access points/routes that will be affected by the work zone or by the traffic control devices will be maintained or by providing acceptable alternate routes.

- Identify all road(s) to be used as a detour route.
- Provide notes regarding all traffic control changes such as temporary signals or signal timing changes required within the work zone or the detour route.
- Typical Sections shall contain all the information listed for Type A Projects.
- Special Details/Cross Sections/Profiles shall contain all the information listed for Type A Projects.
- Public Communications Plan

A Public Communications Plan is required for roadways when traffic volumes exceed the minimum number of vehicles/hour/lane or delay times established by the Regional Operations Director for lane closure periods. The Public Communications Plan shall provide the following information (this information may be presented in a narrative format as part of the Traffic Control Plan or as a separate Special Provision Copied Note):

- All the information listed for Type A Projects.
- A process for notifying Public Safety, Emergency
  Management and mass transit organizations of detour
  route(s) and available alternate routes during
  construction.
- Transportation Operations Plan

A Transportation Operations Plan is required for roadways when the work space is greater than ½ mile in length and/or with reduced width travel lanes. The Transportation Operations Plan shall provide the following information (this information may be presented in a narrative format as part of the Traffic Control Plan or as a separate Special Provision Copied Note):

All the information listed for Type A Projects.

## Type "C" Projects (Significant Projects – Project Management Category V)

These types of projects are anticipated to cause sustained and substantial work zone impacts greater than what is considered tolerable based on policy or engineering judgment. They should be identified early in the design process in cooperation with the FHWA.

Typical Projects: Long duration construction or maintenance projects on Interstate and freeway projects that occupy a location for more than three days with intermittent or continuous lane closures within the following Transportation Management Areas; Northern Virginia (including the counties of Arlington, Alexandria, Fairfax, Loudoun, Prince William, Spotsylvania and Stafford), Richmond (including the City of Richmond, Chesterfield Charles City, Goochland, Hanover, Henrico, New Kent, and

Powhatan Counties as well as the Town of Ashland), Hampton Roads (including the Cities of Chesapeake, Hampton, Newport News, Norfolk, Portsmouth, Virginia Beach and Williamsburg as well as James City and York Counties), and Roanoke Valley (including the cities of Roanoke and Salem as well as Roanoke County). Also includes Interstate and Principle Arterial Roadways with complex multi-phase construction, high accident rates, full closures, or multiple work zones (two or more) within two miles of each other.

- Project Type: Complex project adding additional thru lanes, bridge rehabilitation, interchange construction and reconstruction. Sequence consists of lane closures with several traffic shifts that may include temporary pavement or detours for the duration of the work. Impact of work zone on traffic operations extends beyond the work zone and affects alternate and/or detour routes. Multi phase construction – bridge replacements or new bridges. Rebuilding interchanges with additional ramps or extensive modification to existing ramps.
  - Impact on Traffic: An assessment of the Work Zone Traffic Impact shall be completed using a traffic analysis tool recommended in VDOT's Traffic Operations and Safety Analysis Manual (TOSAM) <a href="http://www.virginiadot.org/business/resources/TOSAM.pdf">http://www.virginiadot.org/business/resources/TOSAM.pdf</a>. Lane closures and detour routes shall comply with the Regional Operation's lane closure policies, with any deviations requiring the approval of the Regional Operations Director.

## Major Components:

#### Temporary Traffic Control Plan

Major components shall consist of Detailed Plans, Typical Sections, and as required Special Details/Cross Sections/Profiles. Each component shall provide the following information per construction phase. This information will be placed on a coordinate plan sheet.

- Detail Plans which include all the information listed for Type B
  Projects including the project's TMP Type as well as a list
  identifying the location of reduced width lane(s) with the width
  reduction specified.
- Typical Sections which include all the information listed for Type B Projects.
- Special Details/Cross Sections/Profiles which include all the information listed for Type B Projects.

#### Public Communications Plan

The Public Communications Plan is required and shall provide all the information required for Type A and B Projects. This information may be presented in a narrative format as part of the Traffic Control Plan or as a separate Special Provision Copied Note.

#### Transportation Operations Plan

The Transportation Operations Plan is required and shall provide all the information required for Type B Projects. (This information may be presented in a narrative format as part of the Traffic Control Plan or as a separate Special Provision Copied Note.)

#### **EXAMPLES**

The following link will open folders containing examples of TMP recommendations and Temporary Traffic Control Plans for previously developed projects. These examples are for illustrative purposes only and may not totally reflect current policy.

http://www.virginiadot.org/business/resources/traffic\_engineering/memos2/Exam ples of Temporary Traffic Control Plans.pdf

#### RESPONSIBILITIES

The following guidance is provided to ensure that all individuals involved in the planning and construction of all work activities within state right of way and on all streets and highways that have been accepted into the State Highway System understand their role and responsibilities in the development, implementation and review of the project's TMP. VDOT personnel, contractors and permittees from the design and construction disciplines/work groups noted below shall have direct responsibilities for the proper development and implementation of the TMP during each preliminary engineering and construction stage of the project.

#### Project Manager

The Project Manager is responsible for following the current Project Management Procedures established by the Project Management Office. In accordance with the Project Management Procedures, the Project Manager will be responsible for ensuring that the project's Transportation Management Plan (TMP) Type for the project is defined at the scoping meeting.

#### Traffic Engineering Division

The Traffic Engineering Division is responsible for providing temporary traffic control standards and work zone guidance and recommendations, as well as identifying and communicating issues related to the design and usage of temporary traffic control devices.

Specific responsibilities of this office include:

- Conducting annual process reviews of two regions each year.
- Evaluating work zone safety by tracking the number of fatalities and injuries in work zones annually.
- Reviewing TMP post-construction reports to ascertain the effectiveness of the TMP and noting the resolution of work zone and/or temporary traffic control problems.

- Revising temporary traffic control standards, procedures and guidance based on the above collected data to improve work zone safety and mobility.
- Defining the appropriate work zone safety training for VDOT personnel, design consultants, construction workers, flaggers, etc.

## Area Construction Engineers

Specific responsibilities of the Area Construction Engineer include:

- Ensuring that the implementation of all TMPs' in the district is in accordance with the plans, specifications, Virginia Work Area Protection Manual and any other pertinent documents.
- Supporting the Work Zone Traffic Control Coordinator and the Region's Work Zone Safety Coordinator(s) in performing their assigned duties.
- Verifying that all contractor personnel are trained and hold valid certifications as required by the Department.
- Advising the appropriate VDOT personnel, as noted in this guidance, of work requiring lane shifts, lane closures and/or phase changes two working days prior to implementing this activity.
- Ensuring that the project's assigned Work Zone Traffic Control Coordinator completes and submits the TMP post-construction report.

## Regional Work Zone Safety Coordinators

The regional work zone safety coordinators are a resource to be utilized by the regional and district staff to ensure that work zones operate safely and efficiently with the least amount of inconvenience and impact to the traveling public. Specific responsibilities of the Regional Work Zone Safety Coordinator include:

- Providing district and regional staff with guidance and recommendations on work zone design and operation.
- Performing work zone reviews to promote consistency and ensure compliance with work zone procedures, standards and guidance.
- Monitoring work zone inspections conducted by field personnel and identifying areas that need improvement.
- Assisting and supporting the project's assigned Work Zone Traffic Control Coordinator in performing their assigned duties

## • Residency Engineers / Administrators

Specific responsibilities of the Residency Engineer/Administrator for project's administered by the residency include:

- Ensuring that residency staff receives the appropriate training related to their duties in the development, implementation and review of Transportation Management Plans (TMP).
- Supporting the Work Zone Traffic Control Coordinator and the Region's Work Zone Safety Coordinator(s) in performing their assigned duties.

- Notifying the Regional Operations Director of work requiring lane closures two working days prior to implementing the lane closure.
- Notifying the Regional Operations Director of height, width and weight restrictions ten working days prior to the imposition of such restrictions.

## Regional/District/Residency Permit Staff

Specific responsibilities of the Regional/District/Residency permit staff include:

- Ensuring that the permittee's temporary traffic control plan is in compliance with this document, VDOT specifications, Virginia Work Area Protection Manual and any other pertinent documents.
- Coordinating lane closure needs and height, width and weight restrictions with the permittee and reporting any requests to the Regional Operations Director two working days prior to the lane closure and ten working days for roadway restrictions before any non-emergency work commences.
- Ensuring that proposed lane closures are in compliance with the regional lane closure policy.

#### Contractor

Specific responsibilities of the contractor include:

- Designating a person assigned to the project who will have the primary responsibility, with sufficient authority, for implementing the TMP.
- Ensuring that contractor personnel assigned to the project are trained in traffic control to a level corresponding with their responsibilities in accordance with VDOT's work zone traffic control training guidelines.
- Advising the appropriate VDOT personnel, as noted in this guidance, work requiring lane shifts, lane closures and/or phase changes two working days prior to implementing this activity.
- Advising the appropriate VDOT personnel, as noted in this guidance, of height, width and weight restrictions ten working days prior to the imposition of such restrictions.
- Performing, at a minimum, daily reviews of the work zone to ensure compliance with contract documents and establish specifications and standards.
- Recommending traffic control improvements to the appropriate VDOT personnel to address field conditions pertaining to traffic flow, visibility, and worker/motorist/pedestrian safety.

#### Permittee

Specific responsibilities of the permittee include:

 Submitting a temporary traffic control plan that prescribes the necessary traffic control measures for the work to be performed. This plan shall have the approval from the appropriate VDOT Permit or Land Development

- office for approval prior to the commencement of work activities within VDOT right of way.
- Identifying a point of contact that shall be available at all times that the permittee is working within the public right of way. This person shall have the training and authority to correct any traffic control deficiencies.
- Designating a person assigned to the project that will have the primary responsibility, with sufficient authority, for implementing the temporary traffic control plan and other safety and mobility aspects of the permit work.
- Ensuring that permittee's personnel assigned to the work activity are trained in traffic control to a level corresponding with their responsibilities in accordance with VDOT's work zone traffic control training guidelines.
- Notifying the appropriate VDOT personnel, two days prior to the commencement of work and prior to implementing lane closures' and ten days prior to the imposition of height, width and weight restrictions.
- Maintaining a copy of the temporary traffic control plan at the work site.
- Performing, at a minimum, daily reviews of the work zone to ensure compliance with temporary traffic control plan and establish specifications and standards.

## Special Provision Copied Notes

The following Special Provision Copied Notes should be included in a project's contract as noted.

- Contractor Alternate Traffic Control Plan All Type B & C Projects and select Type A projects.
- Work Zone Traffic Control Management All Type C Projects and select Type B Projects as determined by the Project Manager. The determination shall be based on traffic volumes, TMP complexity, and need for increased and devoted traffic control management.

#### TRAINING REQUIREMENTS

The Department has established a Work Zone Safety Training Committee (WZSTC) that will present recommendations on procedures, standards, and specifications involving work zone traffic control training issues. The committee will review for approval training courses submitted in compliance with established procedures. The committee will also review and approve Work Zone Traffic Control Training instructor qualifications. Training courses approved in accordance with this procedure shall be the only training accepted as meeting the standards for qualifying persons to plan, design, implement, inspect, and/or

Instructional and Informational Memorandum IIM-LD-241.7 Sheet 20 of 26

supervise the selection, placement, or maintenance of work zone traffic control schemes and devices in work zones on streets and highways within the Commonwealth of Virginia State Highway System right of way. The State Traffic Engineer's Office shall maintain a list of approved courses and their sponsors/providers. The official list of approved courses, category descriptions, and addresses of course sponsors/providers and approved instructors are provided on the Department's Web site at:

http://www.virginiadot.org/business/trafficeng-WZS.asp

# TRANSPORTATION MANAGEMENT PLAN TYPE A PERFORMANCE ASSESSMENT

Project/Permit/Route No.:		Project's PMP Category:	
Report Completed By:		Date of Report:	
VDOT Project/Contract Manager:			
Contractor:			
Please check all applicable boxes for to require comment. This form shall be of the State Traffic Engineer.  Plan Design	he items listed below. All check be completed within 30 days of comple	oxes denoted by an asterisk etion of work and submitted to	
Correct TMP Category Application:	☐ Acceptable ☐ Change	es Required*  Not Applicable	
Correct TTC Plan Application:		es Required*  Not Applicable	
Correct Public Communications Appli			
Correct Traffic Operations Plan Applie			
General Plan Effectiveness:		es Required*  Not Applicable	
Comments:			
Safety			
Crashes*	Yes (Attach FR-300 if a	The state of the s	
Complaints*	Yes (Attach separate sh		
Specification Violations	Yes (Attach CQIP Repo		
Work Zone Safety Reviews:	Yes (Attach Form(s) TE	-97000)	
General Effectiveness:	☐ Acceptable ☐ Change	es Required*	
Comments:			

# Mobility

Driver Expectancy:	☐ Acceptable ☐ Changes Required* ☐ Not Applicable			
Delay & Queue Length* (List time & Length	n): Acceptable Changes Required* Not Applicable			
Travel Times (List time)	☐ Acceptable ☐ Not acceptable* ☐ Not Applicable			
Work Hour Restrictions:	☐ Acceptable ☐ Changes Required* ☐ Not Applicable			
General Effectiveness:	☐ Acceptable ☐ Changes Required* ☐ Not Applicable			
Comments:				
Additional Comments				
Summarize the most successful and least successful work zone traffic control procedures.				
Summarize any suggested improvements or changes to the work zone traffic control procedures for future similar projects.				

# VIRGINIA DEPARTMENT OF TRANSPORTATION

## POST-CONSTRUCTION TRANSPORTATION MANAGEMENT PLAN (TMP) PERFORMANCE ASSESSMENT - TMP Types B and C

This Assessment shall be completed by the project's designated Work Zone Safety Coordinator upon completion of the work and approved by the Project Manager to document lessons learned and provide recommendations on how to improve the TMP process and/or

modify guidelines. The responses should allow the reviewer of this completed Assessment to understand the successes/failures of the project TMP and its requirements. Please attach any relevant documents, project logs, etc. as well as any responses which cannot fit within the provided space.
WORK ZONE INFORMATION:
PROJECT TITLE:
WORK ZONE SAFETY COORDINATOR:
LOCATION:
DISTRICT/REGION:
UPC#
1) Summarize/describe all changes necessary to correct oversights in the TMP:
Summarize/describe all changes made to the original TMP and their level of success:
Describe public reaction to the TMP including the frequency and nature of complaints:

# 4) Summarize travel times encountered during peak periods (if required):

Starting location: Ending location:				
E) Summariza guaya	s encountered during peak periods (if red	united):		

Date	Method Used (i.e., advance warning vehicle)	Queue Length
During-construction average	ge queue length:	
During-construction maxim	um queue length:	
Predicted average/maximu	m queue length from impacts analysis.	

